

Item	Item Description	Quantity	Unit	Unit Cost	Subtotal Cost
1	Site Mobilization	1	LS		\$ -
2	Maintenance of Traffic	1	LS		\$ -
3	As-Built Record Drawings	1	LS		\$ -
4	NPDES Permit	1	LS		\$ -
5	Erosion Control	1	LS		\$ -
6	Indemnification	1	LS		\$ -
7	Unforeseen Condition Allowance	1	LS	\$ 100,000.00	\$ 100,000.00
8	Clearing and Grubbing	1	LS		\$ -
9	1" Type SP-9.5 Asphalt Surface Course	483	SY		\$ -
9A	2" Type SP-9.5 Asphalt Surface Course	50	SY		\$ -
10	6" Compacted Limerock Base or Crushed Concrete	546	SY		\$ -
11	12" Stablized Subgrade	609	SY		\$ -
12	Type "F" Curb	20	LF		\$ -
13	4" Thick Concrete Sidewalk	20	LF		\$ -
14	Curb Ramp with Detectable Warning	2	SY		\$ -
15	Bollards	5	EA		\$ -
16	Guardrail	20	LF		\$ -
17	Swale Grading	637	SY		\$ -
18	Sod	523	SY		\$ -
19	Imported fill	117	CY		\$ -
20	Signing and Striped Crosswalks/Pavement Markings	1	LS		\$ -
21	Solar Powered 2 Beacon Assembly	4	AS		\$ -
	Structural Items				
0455143 2	Piles-Prestressed Concrete, 14" SQ	115	LF		\$ -
0455133 3	Sheet Piling Steel, F&I Permanent	2838	SF		\$ -
0400 2 11	Concrete, Bridge Substructure	31	CY		\$ -
0460 7	Prefabricated Steel Pedestrian Bridge	800	SF		\$ -
0142 70	Fill Sand	31	CY		\$ -
0524 2 2	Concrete Slope Pavement,Non Reinforced, 4"	6	SY		\$ -
				Grand Total	\$ 100,000.00