



Email: Barbara.Lance@colliercountyfl.gov

Telephone: (239) 252-8998

Addendum 4

Date: June 19, 2018
From: Barbara Lance, Procurement Strategist
To: Interested Bidders
Subject: **Addendum #4:** Solicitation # 18-7305 – Master Pump Station 306

The following changes and additional information are hereby made part of the Contract documents:

DRAWINGS:

1. Make Revision to Sheet C-401.
 - a. Update the quantity of Argentine Bahia to 6,800+/- SF in the Plant Schedule.
 - b. Delete "ILE 1" tag located to the west of Thomasson Lane driveway.
 - c. Update the quantity of Southern Magnolias to "2" in Plant Schedule.

SPECIFICATIONS:

1. Specification Section 07 41 13.16 Standing-Seam Metal Roof Panels:
Replace Paragraph 2.2.(B).2.a with the following:
2.2.(B).2.a: Nominal Thickness: 22 gage or 20 gage (0.036 inch nominal)
2. Specification Section 07 52 16 SBS Modified Bitumen Mineral Surfaced Roofing System:
Replace Paragraph 2.6-A. with the following:
2.6-A General: Preformed roof insulation boards manufactured or approved by membrane roofing manufacturer, selected from manufacturer's standard sizes suitable for application, of thicknesses required and that produce FM Approvals-approved roof insulation; and approved by NOA. R Value Required: 19 (average) as long as minimum thickness of 2" is maintained.
3. Specification Section 43 31 16 Diesel Driven Centrifugal Pumps:
Replace Paragraph 2.06 with the following:
2.06-Impellers shall be of the open, 3-bladed, non-clog type with pump out vanes on the back shroud. Dynamically balance the impellers. The impellers shall have a minimum Brinell hardness of 200 HB.

18-7305 Addendum 4 Cont'd

4. Specification 43 31 16 Diesel Driven Centrifugal Pumps:
Delete Paragraph 2.11-A.

C: Wayne Karlovich, Project Manager

Please sign below and return a copy of this Addendum with your submittal for the above referenced solicitation.

(Signature)

Date

(Name of Firm)