

18-7450 Bid Schedule

GOLDEN GATE CITY NORTHWEST QUADRANT SECTIONS 6, 10, AND 11

Pay Item No.	Description	Unit	Quantity	Unit Cost	Total Cost
101-1	MOBILIZATION	LS	1		\$0.00
101-1-1	PROVIDE/MAINTAIN AS-BUILT PLANS	LS	1		\$0.00
101-1-2	PROVIDE CONSTRUCTION SURVEYING AND LAYOUT	LS	1		\$0.00
101-1-3	REPLACE SURVEY MONUMENTS/PROPERTY CORNERS	EA	3		\$0.00
102-1	MAINTENANCE OF TRAFFIC	LS	1		\$0.00
104-11	FLOATING TURBIDITY BARRIER	LF	320		\$0.00
104-18	INLET PROTECTION SYSTEM	EA	61		\$0.00
108-2	MONITOR EXISTING STRUCTURES - VIBRATION MONITORING	LS	1		\$0.00
110-1-1	CLEARING AND GRUBBING (7.7 +/- AC)	LS	1		\$0.00
110-4-10	REMOVAL OF EXISTING CONCRETE (RW AREA)	SY	1,125		\$0.00
110-4-10-A	REMOVAL OF EXISTING CONCRETE SLAB (ESMT AREA)	SY	500		\$0.00
121-70	FLOWABLE FILL	CY	30		\$0.00
CC-1	MAILBOX - RELOCATE	EA	16		\$0.00
CC-2	SWALE REGRADING	LS	1		\$0.00
160-4	TYPE B STABILIZATION (STAGING AREA)	SY	1,040		\$0.00
285-704	OPTIONAL BASE GROUP 4 (6") (Driveway)	SY	453		\$0.00
285-708	OPTIONAL BASE GROUP 8 (9" LIMEROCK, LBR 100)	SY	463		\$0.00
285-709	OPTIONAL BASE GROUP 9 (6" TYPE B-12.5)	SY	764		\$0.00
327-70-6	MILLING EXISTING ASPHALT PAVEMENT (1 1/2" AVG. DEPTH)	SY	7,416		\$0.00
334-1-13-15	SUPERPAVE A.C. (9.5)(TRAFFIC C)(1 1/2") (Roadway)	SY	7,416		\$0.00
334-1-13-155	SUPERPAVE A.C. (9.5)(TRAFFIC C)(1 1/2") (Driveway)	SY	411		\$0.00
425-1-541	INLETS (DITCH BOTTOM TYPE D)(<10')	EA	4		\$0.00
425-1-543	INLETS (DITCH BOTTOM TYPE D)(J BOT<10')	EA	3		\$0.00
425-1-5439	INLETS (DITCH BOTTOM TYPE D)(J BOT <10')(MODIFY)	EA	23		\$0.00
425-1-549	INLETS (DITCH BOTTOM TYPE D)(MODIFY)	EA	31		\$0.00
425-2-91	MANHOLES, J-8, <10'	EA	7		\$0.00
400-1-2	CONCRETE CLASS I, ENDWALLS	CY	46.7		\$0.00
CC-3	REMOVE EXISTING PIPE (0-35")(IN R/W)	LF	2,359		\$0.00
CC-4	REMOVE EXISTING PIPE (36" AND GREATER)(IN R/W)	LF	1,417		\$0.00
CC-5	REMOVE EXISTING PIPE (0-35")(IN ESMT)	LF	1,197		\$0.00
CC-6	REMOVE EXISTING PIPE (36" AND GREATER)(IN ESMT)	LF	2,988		\$0.00
430-175-112	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(12")(IN R/W)	LF	98		\$0.00
430-175-118	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(18")(IN R/W)	LF	1,042		\$0.00
430-175-124	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(24")(IN R/W)	LF	1,014		\$0.00
430-175-130	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(30")(IN R/W)	LF	296		\$0.00
430-175-136	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(36")(IN R/W)	LF	452		\$0.00
430-175-142	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(42")(IN R/W)	LF	303		\$0.00
430-175-148	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(48")(IN R/W)	LF	662		\$0.00
430-175-124-E	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(24")(IN 22' ESM	LF	250		\$0.00
430-175-130-E	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(30")(IN 22' ESM	LF	672		\$0.00
430-175-136-E	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(36")(IN 22' ESM	LF	275		\$0.00
430-175-142-E	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(42")(IN 22' ESM	LF	882		\$0.00
430-175-148-E	PIPE CULVERT (CLASS II PP OR CLASS III CONCRETE)(STORM)(ROUND)(48")(IN 22' ESM	LF	2,106		\$0.00

18-7450 Bid Schedule

GOLDEN GATE CITY NORTHWEST QUADRANT SECTIONS 6, 10, AND 11

Pay Item No.	Description	Unit	Quantity	Unit Cost	Total Cost
CC-7	ADD ESMT PIPE EFFORT (18"-30" PIPE, INSTALLED WITH NO 5' TCE LT/RT)	LF	508		\$0.00
CC-8	ADD ESMT PIPE EFFORT (36"-48" PIPE, INSTALLED WITH NO 5' TCE LT/RT)	LF	1,772		\$0.00
CC-9	REPLACE EXISTING MITERED END SECTION (SIDE DRAIN)(ROUND)(12")	EA	9		\$0.00
520-1-10	CONCRETE CURB & GUTTER, TYPE F	LF	18		\$0.00
522-2	CONCRETE SIDEWALK AND DRIVEWAYS (6" THICK)	SY	1,125		\$0.00
522-2-A	CONCRETE SLAB (6" THICK)(ESMT AREA)	SY	500		\$0.00
526-1-2	PAVERS, ARCHITECTURAL, SIDEWALK (REMOVE AND RESET)	SY	40		\$0.00
527-2	DETECTABLE WARNINGS	SF	12		\$0.00
550-10-218	FENCING (TYPE B)(VARIABLE HEIGHT)(RESET EXISTING)	LF	1,034		\$0.00
550-10-418	FENCING (WOOD)(VARIABLE HEIGHT)(RESET EXISTING)	LF	1,717		\$0.00
550-10-518	FENCING (METAL DECO)(VARIABLE HEIGHT)(RESET EXISTING)	LF	133		\$0.00
550-10-618	FENCING (VINYL)(4' HEIGHT)(RESET EXISTING)	LF	90		\$0.00
550-10-210	FENCING (TYPE B)(VARIABLE HEIGHT)(STANDARD FEATURES)	LF	350		\$0.00
550-10-222	FENCING BLACK CLAD VINYL (TYPE B)(6')(2" ALUM BLACK PRIVACY SLATS)	LF	800		\$0.00
550-10-410	FENCING (WOOD)(VARIABLE HEIGHT)(STANDARD FEATURES)	LF	500		\$0.00
550-10-510	FENCING (METAL DECO)(VARIABLE HEIGHT)(STANDARD FEATURES)	LF	50		\$0.00
550-10-610	FENCING (VINYL)(VARIABLE HEIGHT)(STANDARD FEATURES)	LF	35		\$0.00
550-10-810	FENCING (TEMP TYPE B)(VARIABLE HEIGHT)(STANDARD FEATURES)	LF	1,000		\$0.00
550-60-211	FENCE GATE (TYPE B)(SINGLE)(0-6.0' OPENING)	EA	3		\$0.00
550-60-224	FENCE GATE, BLACK CLAD VINYL (TYPE B) (DUAL, 6'-H x 20'-W)(2" ALUM BLACK SLAT	EA	2		\$0.00
550-60-411	FENCE GATE (WOOD)(SINGLE)(0-6.0' OPENING)	EA	4		\$0.00
550-60-511	FENCE GATE (METAL DECO)(SINGLE)(0-6.0' OPENING)	EA	1		\$0.00
550-60-611	FENCE GATE (VINYL)(SINGLE)(0-6.0' OPENING)	EA	1		\$0.00
570-1-2	PERFORMANCE TURF (SOD) (BAHIA)	SY	6,969		\$0.00
570-1-6	PERFORMANCE TURF (SOD) (FLORATAM)	SY	10,250		\$0.00
700-1-50	SINGLE POST SIGN (RELOCATE)	AS	4		\$0.00
CC-10	PAVEMENT MARKING RESTORATION	LS	1		\$0.00
CC-11	MODIFY INLET TO UTILITY CONFLICT BOX	EA	2		\$0.00
CC-12	POTHOLE AT FPL POLE HOLD LOCATIONS	EA	4		\$0.00
CC 950-LND	LANDSCAPING ALLOWANCE	FIXED	1	\$90,000.00	\$90,000.00
CC 950-RDW	DRAINAGE ALLOWANCE	FIXED	1	\$225,000.00	\$225,000.00
		BASE BID			\$315,000.00
CC-13	CALUSIA GUTTIFERA HEDGE PLANTINGS (7-GAL)(ON 2' CENTERS)	LF	2,000		\$0.00
		BID ALTERNATE			\$0.00
		BASE BID + BID ALTERNATE			\$315,000.00