



COUNTY OF CHARLOTTE PURCHASING DIVISION

Charlotte County Administration Center
18500 Murdock Circle
Port Charlotte, Florida 33948-1094
(941) 743-1378

via fax

TO: PROSPECTIVE BIDDERS
DATE: November 8, 2018
RE: ADDENDUM #2 BID NO. 2019000063 – STORMWATER CONTROL STRUCTURE HAVERHILL 4.84 WATERWAY

BID OPENING DATE: 2:00 p.m. (EST) NOVEMBER 28, 2018

Bidders are hereby notified that this Addendum shall be made a part of the documents. The intent is to add to, modify, or clarify the documents. Should any of these items have an effect on price, such changes shall be included in the price bid. These items have the same force and effect as if contained in the original.

ITEM #1: REVISIONS

TS-28 PULL & JUNCTION BOX: REMOVE: Bid Item No. 635-2-40 Pull & Slice Box (Modify) Each (EA)

ITEM #2: REVISIONS

TS-29 ALUMINUM SIGNALS POLE: REVISE: A. GENERAL to read:

- A. GENERAL - The work specified in this Technical Specification consists of furnishing and the installation of aluminum pedestrian pedestal assemblies **and removal** as indicated in the plans. Installation of aluminum pedestrian assemblies shall conform to the requirements of the latest edition at time of design of Design Standards of the Florida Department of Transportation Design Standards Standard, and the Charlotte County Supplemental Specifications for Traffic Signal Installations, except as amended herein. The link to the Charlotte County Supplemental Specification is provided.

ITEM #3: REVISIONS

TS29 ALUMINUM SIGNALS POLE: ADD: Bid Item No 646-1-60 Aluminum Signal Pole Removal Each (EA)

ITEM #4: REVISED BID FORM – Revised Bid Form Page 55

NOTE TO BIDDER: Please make sure, REVISED BID FORM PAGE 55, included in Addenda #5 is used when submitting the bid. Otherwise bid will be deemed non-responsive for incorrect bid form submittal.

This addendum is binding and is to be considered as if contained within the original bid documents of Bid No. 2019000063. Bidders are required to acknowledge receipt of this addendum on their bid forms.


Kimberly A. Corbett, C.P.M., CPPB
Senior Division Manager Purchasing

KAC/vs

cc: Karen Bliss, Project Manager
File

Bid No. 2019000063 Addenda #2

RFB 2019000060 SUMMARY OF PAY ITEMS REVISED ADDENDA #2

PEDESTRIAN SIGNAL & PAVEMENT MARKINGS

| | | | | | |
|----------------------|--|----|---------------------|----|----|
| 630-2-11 | OPEN TRENCH, (F&I) CONDUIT | LF | 33 | \$ | \$ |
| 630-2-12 | DIRECTIONAL BORE, (F&I) CONDUIT | LF | 49 | \$ | \$ |
| 632-7-1 | SIGNAL CABLE, (F&I) NEW OR RECONSTRUCTED | PI | 1 | \$ | \$ |
| 635-2-11 | PULL & SPICE BOX, (F&I) 17"X30" COVER SIZE | EA | 3 | \$ | \$ |
| 646-1-11 | ALUMINUM SIGNALS POLE | EA | 4 | \$ | \$ |
| 646-1-60 | ALUMINUM SIGNALS POLE (REMOVAL) | EA | 2 | \$ | \$ |
| 653-1-11 | PEDESTRIAN SIGNAL, (F&I), (LED COUNTDOWN), (1 WAY) | AS | 2 | \$ | \$ |
| 653-1-12 | PEDESTRIAN SIGNAL, (F&I), (LED COUNTDOWN), (2 WAY) | AS | 2 | \$ | \$ |
| 665-1-11 | PEDESTRIAN DETECTOR, (F&I) STANDARD (POLE MOUNTED DETECTOR STATION) FTP-68B-06 | EA | 5 | \$ | \$ |
| 670-5-400 | TRAFFIC CONTROLLER ASSEMBLY (MODIFY) | AS | 1 | \$ | \$ |
| 700-46-21 | ROADSIDE SIGN, (RELOCATE) | EA | 8 | \$ | \$ |
| 706-3 | RETRO-REFLECTIVE PAVEMENT MARKERS | EA | 20 | \$ | \$ |
| 710-11-121 | SOLID TRAFFIC STRIPE 6" PAINTED WHITE | LF | 712 | \$ | \$ |
| 710-11-123 | SOLID TRAFFIC STRIPE 12" PAINTED WHITE | LF | 241 | \$ | \$ |
| 710-11-125 | SOLID TRAFFIC STRIPE 24" PAINTED WHITE | LF | 11 | \$ | \$ |
| 710-11-221 | SOLID TRAFFIC STRIPE 6" PAINTED YELLOW | LF | 714 | \$ | \$ |
| MISCELLANEOUS | | | | | |
| TS-36 | EMERGENCY BYPASS | EA | 2 | \$ | \$ |
| TS-37 | AS-BUILT SURVEY DRAWINGS | LS | 1 | \$ | \$ |
| UTILITIES | | | | | |
| U-329 | 20" DIP FM CL-51 CL151/C153 DR-18 | LF | 295 | \$ | \$ |
| U-276 | 20" ALL OTHER TYPE PIPE REMOVAL | LF | 295 | \$ | \$ |
| U-391 | 20" TIE BACK ASSEMBLY | EA | 2 | \$ | \$ |
| U-354 | 20" PLUG VALVE | EA | 2 | \$ | \$ |
| U-362 | 20" WET TAPING VALVE, 20" pipe X 20" tap | EA | 2 | \$ | \$ |
| U-305 | 12" ASBESTOS PIPE REMOVAL | LF | 348 | \$ | \$ |
| U-14 | 12" PVC WM C900/C905 CL 150, DR18* | LF | 348 | \$ | \$ |
| U-188 | 12" TIE BACK ASSEMBLY | EA | 1 | \$ | \$ |
| U-46 | DUCTILE IRON FITTINGS | LB | 2500 | \$ | \$ |
| U-10 | LINE STOPPING PLUG (FM) | EA | 2 | \$ | \$ |
| | TEMPORARY SAMPLE POINTS* | EA | 2 | \$ | \$ |
| | | | SUB-TOTAL \$ | | |

*NOTE: THE COST OF TEMPORARY SAMPLE POINTS, AND TESTING IS INCLUDED IN ITEM U-14

Item 101-1: Mobilization/Demobilization: The cost for mobilization/demobilization shall be five percent (5%) of the sub-total project cost.

SUBTOTAL \$ _____ X 5% = \$ _____

TOTAL BID PRICE \$ _____

Name of Bidder: _____

(This page to be returned)