

**Polk County Utilities Community Investment Project
Ernie Caldwell Reclaimed Water Main Improvements Phase One
BID # 19-340**

ADDENDUM 2 REVISED BID SHEET

	Description	Unit	Quantity	Unit Price	Total Cost
1	Reclaimed Water Main				
1a	20" PVC (Open Cut)	LF	7,350		\$ -
1b	20" Ductile Iron, Pressure Class 250 (Open Cut)	LF	30		\$ -
2	Wastewater Force Main				
2a	20" PVC	LF	170		\$ -
3	Fittings				
3a	20" x 20" Tee, RMJ	EA	1		\$ -
3b	20" x 12" Tee, RMJ	EA	2		\$ -
3c	20" x 8" Reducer, RMJ	EA	1		\$ -
3d	20" 11.25 Degree Bend, RMJ	EA	14		\$ -
3e	20" 45 Degree Bend, RMJ	EA	23		\$ -
3f	20" 90 Degree Bend, RMJ	EA	1		\$ -
3g	12" 45 Degree Bend, RMJ	EA	2		\$ -
3h	8" 90 Degree Bend, RMJ	EA	2		\$ -
3i	8" 45 Degree Bend, RMJ	EA	2		\$ -
3j	20" Cap, RMJ	EA	9		\$ -
3k	12" Cap, RMJ	EA	2		\$ -
4	Valves and Appurtenances				
4a	20" Gate Valve & Box	EA	12		\$ -
4b	12" Gate Valve & Box	EA	2		\$ -
4c	8" Gate Valve & Box	EA	1		\$ -
4d	4" Blow Off Valve and Enclosure	EA	1		\$ -
4e	4" Air Release Valve and Enclosure	EA	11		\$ -
5	Fire Hydrant Service Lateral Relocation				
5a	6" 90 Degree Bend, RMJ	EA	1		\$ -
5b	6" 45 Degree Bend, RMJ	EA	4		\$ -
5c	6" Gate Valve & Box	EA	1		\$ -
6	Connection to Existing Reclaimed Water Main				
6a	20" Connection	EA	1		\$ -
6b	8" Connection	EA	1		\$ -
7	Horizontal Directional Drill				
7a	20" HDPE HDD	LF	1,880		\$ -
8	Jack & Bore				
8a	20" PVC w/36" Steel Casing (Jack & Bore)	LF	110		\$ -
9	RCW Main within Steel Casing				
9a	36" Steel Casing (Open Cut)	LF	60		\$ -
10	Seed & Mulch	LF	9,370		\$ -
11	Concrete Sidewalk Removal and Replacement	SY	180		\$ -
12	8" Concrete Pad	CY	90		\$ -
13	Chain Link Fence	LF	140		\$ -
14	Restore Gravel Access Drive with No. 57 Aggregate	CY	6		\$ -
15	Abandon Existing Pipe				
15a	Grout 8" Reclaimed Water Main	LF	1,290		\$ -
16	Prevention, Control, & Abatement of Erosion/Water Pollution	LS	1		\$ -
17	Pipe Line Marker	EA	24		\$ -
18	Asphalt Milling & Resurface	SY	20		\$ -
19	Concrete Curb and Gutter Removal and Replacement	LF	31		\$ -
20	Gopher Tortoise Survey	LS	1		\$ -
21	Mobilization/Demobilization	LS	1		\$ -
22	Maintenance of Traffic	LS	1		\$ -
23	Contingency for Replacing Unsuitable Soil with Suitable Fill	LS	1	\$25,000	\$25,000
24	Contingency for Unforeseen Conditions	LS	1	\$25,000	\$25,000
	GRAND TOTAL				\$50,000