

**COLLIER COUNTY  
 BID SCHEDULE SUMMARY  
 CENTRAL MARCO ISLAND REGRADE - 2018**

Item Number	Item Description	Estimated Quantity	Unit	Unit Cost	Total Cost
1	Mobilization and Demobilization	1	Job	L.S.	\$ _____
2	Option A: Dredging; Fill Placement (155,000 CY Approx.) from R-135 to R-139.5; Grading; Proof-Rolling and Rolling (1' lifts); Survey Control and Progress Surveys (Pre and Post Construction); Turbidity Control and Monitoring; Restoration of Construction Access and Staging Area.	1	Job	L.S.	\$ _____
				Option A Subtotal Base Bid:	\$ _____
3	Option B: Dredging; Fill Placement (20,000 CY Approx.) from R-139.5 to R-141.5; Grading; Proof-Rolling and Rolling (1' lifts); Survey Control and Progress Surveys (Pre and Post Construction); Turbidity Control and Monitoring; Restoration of Construction Access and Staging Area.	1	Job	L.S.	\$ _____
				Option B Subtotal Base Bid:	\$ _____
				Option A & B Total Base Bid:	\$ _____
4	Option C: Additional Dredging as Requested by the County Due to Updated Conditions; Fill Placement; Grading; Proof-Rolling and Rolling (1' lifts); Survey Control and Progress Surveys (Pre and Post Construction); Turbidity Control and Monitoring; Restoration of Construction Access and Staging Area.	Not to Exceed 45,000 cubic yards	Cubic Yards	\$ _____	

**Notes:**

- I. Quantities listed above are estimates and subject to change.
- II. Progress survey(s) are along Stations spaced at 200' as shown on plans to document pre and post construction condition for payment.
- III. Completed fill template is a lump sum pay item and therefore not paid per volume of sand required. The estimated quantities do not account for compaction, shrinkage, etc.
- IV. Reference monuments range is approximate. See plans for actual range of fill template.