

19-7611 Bid Schedule

**Collier County EPMD PROJECT No.: 70123.5.1
U.S. 41 WATER MAIN REPLACEMENT**

Item No.	Item Description	QTY	Unit	Unit Price	Bid Total
SECTION 1: GENERAL					
1.1	Mobilization/Demobilization (Max 10% of Base Bid Total)	1	LS		\$ -
1.2	Maintenance of Traffic	1	LS		\$ -
1.3	Survey Layout & Record Drawings	1	LS		\$ -
1.4	Erosion and Sedimentation Control	1	LS		\$ -
1.5	Pre-Construction Video & Photographs	1	LS		\$ -
SECTION 1 SUBTOTAL:					\$ -
SECTION 2: WATER					
2.1	Water Main Installation				
a.	8" C900 PVC Open Cut	300	LF		\$ -
b.	10" PVC Slot Trench/Open Cut/Hand Dig	720	LF		\$ -
c.	10" HDPE Slot Trench/Open Cut/Hand Dig	2530	LF		\$ -
d.	10" HDPE Pipe Bursting	2530	LF		\$ -
e.	10" HDPE Directional Drill	1150	LF		\$ -
2.2	Gate Valves and Boxes				
a.	6--inch Gate Valve	11	EA		\$ -
b.	8-inch Gate Valve	11	EA		\$ -
c.	10-inch Gate Valve	15	EA		\$ -
d.	6" Insert Valve	13	EA		\$ -
e.	8" Insert Valve	3	EA		\$ -
f.	12" Insert Valve	2	EA		\$ -
2.3	Line Stop				
a.	6" Line Stop	11	EA		\$ -
b.	8" Line Stop	3	EA		\$ -
2.4	Air Release Valves	11	EA		\$ -
2.5	Fire Hydrant Assemblies	15	EA		\$ -
2.6	Temporary Bacteriological Sample Points	17	EA		\$ -
2.7	Connection to Existing Water Main	22	EA		\$ -
2.8	Grout/Abandon Existing Water Main	7,250	LF		\$ -
SECTION 2 SUBTOTAL:					\$ -
SECTION 3: WASTEWATER					
3.1	Sewer Lateral Relocation				
a.	Lateral Relocation 1 (Milan Center - 9465 Tamiami Trail N)	1	LS		\$ -
b.	Lateral Relocation 2 (North Naples Car Wash - 10101 Tamiami Trail N)	1	LS		\$ -
c.	Lateral Relocation 3 (7-Eleven - 10795 Tamiami Trail N)	1	LS		\$ -
d.	Lateral Relocation 4 (North Collier Animal Clinic - 10895 Tamiami Trail N)	1	LS		\$ -
3.2	Precast Polymer Concrete Manhole	7	EA		\$ -
3.3	Abandon Existing Conflict Box	1	EA		\$ -
3.4	Abandon/Dispose Manhole	7	EA		\$ -
3.5	Abandon/Dispose Existing Gravity Main	2000	LF		\$ -
SECTION 3 SUBTOTAL:					\$ -
SECTION 4: ROAD RESTORATION					
4.1	Remove, Dispose, and Replace Driveway				
a.	Asphalt Driveway (Remove, Dispose, Replace)	60	SY		\$ -
b.	Reinforced Concrete Driveway (Remove, Dispose, Replace)	125	SY		\$ -
4.2	Remove, Dispose, and Replace Sidewalk	75	SY		\$ -
4.3	Remove, Dispose, and Replace Concrete Curb and Gutter	1400	LF		\$ -
4.4	Road Restoration - Stabilized Subgrade	1600	SY		\$ -
4.5	Road Restoration - Limerock Base	1200	SY		\$ -
4.6	Road Restoration - Flowable Fill	1200	SY		\$ -
4.7	Road Restoration 2-1/2" Asphalt (Two Lifts)	1100	SY		\$ -
4.8	Milling & Resurfacing	1150	SY		\$ -
SECTION 4 SUBTOTAL:					\$ -
SECTION 5: ALLOWANCES					
5.1	Owner Directed Allowance	1	TBD	\$ 200,000.00	\$ 200,000.00
TOTAL					\$ 200,000.00

Yes/No

Bid Response Form (Form 1)		
Exhibit N - Contractors Key Personnel Assigned to the Project - (Form 2)		
Material Manufacturers (Form 3)		
List of Major Subcontractors (Form 4)		
Statement of Experience of Bidder (Form 5)		
Trench Safety Act Acknowledgement (Form 6)		
Bid Bond (Form 7)		
Insurance and Bonding Requirements (Form 8)		
Conflict of Interest Affidavit (Form 9)		
Vendor Declaration Statement (Form 10)		