

**Collier County Public Utilities Department
Waste Water Division**

**North County Water Reclamation Treatment Facility (NCWRF)
Lifeline Fall Protection System Project
Bid Tab Sheet**

Scope of work

1	43 – NCWRF – NCWRF MLE Aeration Basin: The purpose is to replace the existing Flexible Lifeline System that includes thirteen (13) Multi-Span Fall Protection Systems {2468 (1-13)} and thirteen (13) DBI Sala Horizontal Lifeline Fall Protection Systems 15637 (1-13). Refer to attached Certificate of Inspection. Contractor shall design, engineer and install thirteen (13) 241' Overhead Cable Lifeline Fall Protection Systems utilizing the existing Flexible Lifeline Systems (FLS) lifeline end components. Each cable lifeline shall be supported by attaching directly to the existing lifeline support columns. Contractor shall install new intermediate connections to the existing columns. Each cable lifeline shall be designed to support up to two (2) users. Utilize the existing trolleys and SRL's from previous project.
2	60 – NCWRF – Aerated Sludge Holding Tank: The purpose is to replace the existing Flexible Lifeline System that includes five (5) DBI Sala Horizontal Lifeline Fall Protection Systems 15637 (14-18). Refer to attached Certificate of Inspection. Contractor shall design, engineer and install two (2) 140' Overhead Cable Lifeline Fall Protection Systems and three (3) 150' Overhead Cable Lifeline Fall Protection Systems. Each cable lifeline shall be supported by attaching directly to the existing lifeline support columns. Contractor shall install a total of ten (10) compression braces to the end column supports (one (1) at each end column support). Each cable lifeline shall be designed to support up to two (2) users. Furnish ten (10) new lifeline trolleys.

	Description	Unit	Cost
1	Mobilization	LS	
2	General Conditions	LS	
Sub-Total Cost			\$0.00

43 – NCWRF – Aeration Basin

1	Thirteen (13) 241' Overhead Cable Lifeline Fall Protection Systems	LS	
Sub-Total Cost			\$0.00

60 – NCWRF – Aerated Sludge Holding Tank

1	Two (2) 140' Overhead Cable Lifeline Fall Protection Systems	LS	
2	Three (3) 150' Overhead Cable Lifeline Fall Protection Systems	LS	
3	Ten (10) Compression Braces	LS	
4	Ten (10) Lifeline Trolleys	LS	
Sub-Total Cost			\$0.00

Allowance

1	Allowance for unforeseen conditions such as unmarked utilities, etc.	TM	\$10,000
----------	--	----	----------

Base Bid