

QUOTE SCHEDULE VANDERBILT DRIVE STORMWATER OUTFALL RECOVERY

Request #:

Bidder:

Temporary Repairs					
Item Number	Description	Unit	Bid Quantity	Unit Price	Contract Amount
101-1	Mobilization	LS	1		\$ -
102-1	Maintenance of Traffic	LS	1		\$ -
104-10-3	Sediment Barrier	LF	170		\$ -
104-11	Floating Turbidty Barrier	LF	80		\$ -
104-18	Inlet Protection System	EA	2		\$ -
110-1-1	Clearing and Grubbing	AC	2		\$ -
110-4-10	Removal of Existing Concrete	SY	18		\$ -
120-1	Excavation	CY	106		\$ -
121-70-1	Flowable Fill	CY	10		\$ -
142-70	Sand Fill	CY	944		\$ -
160-4	Type B Stabilization	SY	212		\$ -
230-2	Limerock Material, 6" Sidewalk	CY	305		\$ -
285-709	Optional Base, Base Group 9	SY	69		\$ -
334-1-13	Superpave Asphaltic Concrete (Traffic C) 3"	TN	35		\$ -
400-4-8	Concrete Class IV, Bulkhead	CY	5		\$ -
415-1-6	Reinforcing Steel, Anchor Bar Tiebacks	LB	1102		\$ -
415-1-8	Reinforcing Steel, Seawall Cap	LB	744		\$ -
425-11	Modify Existing Drainage Structure	EA	4		\$ -
430-94-1	Desilting Pipe, 0-24"	LF	264		\$ -
430-94-2	Desilting Pipe, 24-36"	LF	72		\$ -
430-175-115	Pipe Culvert, Optional Material, 15" Round, S/CD	LF	72		\$ -
430-175-115	Pipe Culvert, Optional Material, 12"x18" ERCP	LF	252		\$ -
430-175-136	Pipe Culvert, Optional Material, 36" Round, S/CD	LF	48		\$ -
430-175-230	Pipe Culvert, Optional Material, 24"x36" ERCP	LF	72		\$ -
430-963-2	PVC Pipe for Non-Standard Drainage	LF	224		\$ -
430-982-623	Mitered End Section, Optional-Elliptical, 12"x18" S/CD	EA	6		\$ -
530-3-4	Rubble Rip Rap, Ditch Lining	TN	27		\$ -
530-75	Rock Drain, 57-Stone	TN	1		\$ -
570-1-1	Performance Turf	SY	1284		\$ -
				Subtotal:	\$ -
999-999	Project Allowance (20%)	FIXED	1		\$ -
				Temporary Repairs Total:	\$ -