



Davidson Engineering  
 4365 Radio Road, Suite 201  
 Naples, FL 34104

**Collier County Agriculture Center - IFAS**

6/1/2018

**Bid Schedule - Proposed Site Work**

Scope of Work		Quantity	Unit	Unit Price	Total Price
<b>Initial Site Design</b>					
1	Mobilization	1	LS		\$ -
2	Silt Fence	415	LF		\$ -
3	Maintenance of Traffic	1	LS		\$ -
4	Removal of Existing Asphalt	375	SF		\$ -
4	Removal of Existing Fire Utilities	1	LS		\$ -
5	Removal / Demolition of Existing Fire Pump Bldg.	1	LS		\$ -
6	Survey Stake-out	1	LS		\$ -
7	As-builts	1	LS		\$ -
8	Testing (Density)	1	LS		\$ -
9	Grading (Rough and Final)	1	LS		\$ -
10	Sod (Bahia)	1	LS		\$ -
<b>TOTAL INITIAL SITE DESIGN CONSTRUCTION</b>					<b>\$ -</b>
<b>Pavement</b>					
11	Asphalt - 2" Type S-III (Two Lifts)	42	SY		\$ -
12	Black Base	44	SY		\$ -
13	Striping (Stop Bar)	1	LS		\$ -
14	Signage (Stop Sign)	1	EA		\$ -
<b>TOTAL PAVEMENT CONSTRUCTION</b>					<b>\$ -</b>
<b>Water Utilities - C900 CL150 DR 18 &amp; CL200 DR-14 PVC</b>					
15	10" Water / Fire Main	24	LF		\$ -
16	6" Water / Fire Main	584	LF		\$ -
17	4" Water Service	590	LF		\$ -
18	Fittings: Lump Sum for Proposed Site	1	LS		\$ -
19	Relocate Existing 10" Blow-off	1	LS		\$ -
20	Fire Hydrant Assembly w/Valve	1	EA		\$ -
21	Check Valve	1	EA		\$ -
22	6" N-Style BF Device / Detector Check	1	EA		\$ -
23	Fire Department Connection	1	EA		\$ -
24	6" PIV	1	EA		\$ -
25	Gap Configuration / Temp BF Device	1	EA		\$ -
26	10" Gate Valve	1	EA		\$ -
27	6" Gate valve	1	EA		\$ -
28	Connection to Existing 10" Watermain	1	LS		\$ -
<b>TOTAL WATER UTILITY CONSTRUCTION</b>					<b>\$ -</b>
<b>Misc. Conditions (If Necessary)</b>					
29	Removal of Existing Trees	1	EA		\$ -
30	4' Chain Link Fence Replacement	1	LF		\$ -
31	Irrigation Removal and Replacement	1	LS		\$ -
32					\$ -
33					\$ -
34					\$ -
35					\$ -
36					\$ -
37					\$ -
38					\$ -



Davidson Engineering  
4365 Radio Road, Suite 201  
Naples, FL 34104

<b>TOTAL MISC. CONDITIONS CONSTRUCTION</b>	<b>\$</b>	<b>-</b>
<b>OVERALL TOTAL SITE CONSTRUCTION</b>	<b>\$</b>	<b>-</b>