

**1. Oil Well Road Right of Way;**

Along Oil Well Road clear, grub and grade a total of 11.72 acres. Final grade will be based on fill material located within the area to be cleared. Silt fence will be installed by others however the chosen contractor will be responsible for maintaining the silt fence in good condition throughout the course of this work. All clearing and grubbing materials to be hauled off site. Grassing will be handled by Neal Communities and is not part of this work.

**2. Big Cypress Basin Access Easement Area;**

Along the west property line clear, grub, grade and sod with Bahia a total of 2.42 acres. Final grade will be based on fill material on site. Silt fence will be installed by others however the chosen contractor will be responsible for maintaining the silt fence in good condition throughout the course of this work. All materials to be hauled off site.

**3. Faka Union Canal Frontage;**

Along the east side of the Faka Union Canal, Hydro-axe all exotic vegetation down to existing grade [\(2.22 acres\)](#). Contractor will be responsible for installing turbidity barrier along the canal as needed. No materials to be left in the canal. Turbidity barrier to be removed after the work is complete. Silt fence will be installed by others along the eastern side of this work area however the chosen contractor will be responsible for maintaining the silt fence in good condition throughout the course of this work.