

BID SCHEDULE - PHASE 2 PELICAN BAY SIDEWALK IMPROVEMENTS

BIDDER: _____

Item No.	FDOT Item No.	Description	Unit	Quantity	Unit Cost	Total Cost
1	0101 1	MOBILIZATION	LS	1	\$0.00	\$0
2	0102 1	MAINTENANCE OF TRAFFIC	LS	1	\$0.00	\$0
3	0101 1 1	PROVIDE CONSTRUCTION SURVEYING AND LAYOUT	LS	1	\$0.00	\$0
4	0101 1 2	AS-BUILT RECORD DRAWINGS	LS	1	\$0.00	\$0
5	104-10-1	EROSION CONTROL	LS	1	\$0.00	\$0
6	0104 7	SEDIMENT CONTAINMENT SYSTEM	EA	175	\$0.00	\$0
7	0104 10 3	SILT FENCE	LF	56,900	\$0.00	\$0
8	0110 1 1	CLEARING AND GRUBBING	LS	1	\$0.00	\$0
9	-	REMOVAL OF EX. SIDEWALK ASPHALT PAVEMENT (EXCAVATION & DISPOSAL)	SY	31,803	\$0.00	\$0
10	0110 4 10	REMOVAL OF EXISTING CONCRETE (CURBS & CONC. SIDEWALK PANELS)	SY	1,626	\$0.00	\$0
11	0526 1101	*REMOVAL OF EX. PAVERS & REINSTALL W/ NEW SAND & BASE (Driveway Aprons)	SY	508	\$0.00	\$0
12	-	REMOVAL OF EXISTING ASPHALT & LIMEROCK BASE (Asphalt Driveway)	SY	47	\$0.00	\$0
13	-	ASPHALT DRIVEWAY RESTORATION (8" Limerock Base)	SY	47	\$0.00	\$0
14	-	ASPHALT DRIVEWAY RESTORATION (1" SP-9.5 Asphalt & 1.5" SP-12.5 FC)	SY	47	\$0.00	\$0
15	-	MILL & OVERLAY EXISTING ASPHALT DRIVEWAYS	SY	103	\$0.00	\$0
16	0522 2	CONCRETE SIDEWALK, 6" THICK PORTLAND CEMENT W/ FIBER MESH 3,000 PSI	SY	40,958	\$0.00	\$0
17	-	REMOVE EXISTING PAVERS AT DRIVEWAYS (FOR NEW SIDEWALK CORRIDOR)	SY	2,595	\$0.00	\$0
18	0520 3	3' VALLEY GUTTER RAMP & TRANSITION (INCLUDES ASPHALT PATCHING)	LF	2,783	\$0.00	\$0
19	0520 2 4	SIDEWALK CURB	LF	506	\$0.00	\$0
20	0527 2	DETECTABLE WARNINGS (CAST IN PLACE)	SF	3,501	\$0.00	\$0
21	0570 1 2	PERFORMANCE TURF (SOD -INCLUDES WATER, FERTILIZER & MOWING)	SY	70,400	\$0.00	\$0
22	0700 1 50	SINGLE POST SIGN (RELOCATE W/ BASE)	EA	91	\$0.00	\$0
23	-	THERMOPLASTIC PAVEMENT MARKING REMOVAL	LF	1,242	\$0.00	\$0
24	0711 11123	THERMOPLASTIC (STANDARD)(WHITE)(SOLID)(12") (INCL. INITIAL PAINT)	LF	7,486	\$0.00	\$0
25	0711 11125	THERMOPLASTIC (STANDARD)(WHITE)(SOLID)(24") (INCL. INITIAL PAINT)	LF	834	\$0.00	\$0
26	0526 1 1	CLAY BRICK PAVERS (WHITE, INCLUDES CUT & REMOVAL OF EXISTING)	SF	1,904	\$0.00	\$0
27	0425 6	ADJUST WATERMAIN VALVE TO GRADE	EA	33	\$0.00	\$0
28	0590 70 1	IRRIGATION SYSTEM REPAIRS & RESTORATION (ALLOWANCE)	LS	1	\$0.00	\$0
29	0110 23	LANDSCAPE - TREE REMOVAL (PALM)	EA	60	\$0.00	\$0
30	0110 23	LANDSCAPE - TREE REMOVAL (HARDWOOD OAK)	EA	41	\$0.00	\$0
31	0110 23	LANDSCAPE - TREE REMOVAL (MAHOGANY)	EA	13	\$0.00	\$0
32	0110 23	LANDSCAPE - TREE REMOVAL (PINE)	EA	3	\$0.00	\$0
33	0110 23	LANDSCAPE - TREE REMOVAL (BLACK OLIVE)	EA	6	\$0.00	\$0
34	0110 23	LANDSCAPE - TREE REMOVAL (TABEBUIA)	EA	7	\$0.00	\$0
35	0110 23	LANDSCAPE - TREE REMOVAL (INDIAN ROSEWOOD)	EA	5	\$0.00	\$0
36	0110 23	LANDSCAPE - TREE REMOVAL (HONG KONG ORCHID)	EA	4	\$0.00	\$0
37	0110 23	LANDSCAPE - TREE REMOVAL (GUMBO LIMBO)	EA	3	\$0.00	\$0
38	0110 23	LANDSCAPE - TREE REMOVAL (FICUS)	EA	1	\$0.00	\$0
39	0110 23	LANDSCAPE - TREE REMOVAL (DALBERGIA)	EA	1	\$0.00	\$0
40	0110 23	LANDSCAPE - TREE REMOVAL (BAULANIA)	EA	1	\$0.00	\$0
41	0110 23	LANDSCAPE - TREE REMOVAL (CHINABERRY)	EA	1	\$0.00	\$0
					SUBTOTAL	\$0
			OWNER'S ALLOWANCE	T&M		\$600,000
					TOTAL BID	\$600,000