

Bid Schedule
ITB No. 23-8058
Golden Gate City Transmission Water Main Improvements - Phase 1A - Golf Course

SECTION 1: GENERAL					
ITEM NO.	DESCRIPTION	EST. QUANT	UNIT	UNIT PRICE	EXTENDED PRICE
1	Mobilization/Demobilization	1	LS		\$ -
2	Maintenance of Traffic	1	LS		\$ -
3	Survey Layout & Record Drawings	1	LS		\$ -
4	Pre-Construction Video	1	LS		\$ -
5	Project Sign	1	LS		\$ -
SECTION 1 SUBTOTAL:					\$ -
SECTION 2: WATER SYSTEM					
ITEM NO.	DESCRIPTION	EST. QUANT	UNIT	UNIT PRICE	EXTENDED PRICE
6	Water Main Pipelines (Via Open-Cut)				
a.	6-inch PVC DR18	20	LF		\$ -
b.	8-inch PVC DR18	33	LF		\$ -
c.	10-inch PVC DR18	10	LF		\$ -
d.	12-inch PVC DR18	325	LF		\$ -
e.	24-inch DIP (Pipe Material Purchased by COUNTY)	6,360	LF		\$ -
7	Water Main Pipelines (Via Horizontal Directional Drill)				
a.	24-inch HDPE DR11 (Pipe Material Purchased by COUNTY) Collier Blvd #1 (Entry to Exit = 492 L.F.)	1	LS		\$ -
8	Connect to Existing Water Main				
a.	36-inch PCCP WM (Cut In Existing)	1	EA		\$ -
9	Air Release Valve	3	EA		\$ -
10	Fire Hydrant Assembly	5	EA		\$ -
11	Leak Detection Device	1	EA		\$ -
12	Gate Valve (Valves Purchased by COUNTY)				
a.	8-inch Gate Valve	2	EA		\$ -
b.	10-inch Gate Valve	1	EA		\$ -
c.	12-inch Gate Valve	2	EA		\$ -
d.	24-inch Gate Valve	7	EA		\$ -
e.	36-inch Gate Valve	1	EA		\$ -
13	Permanent Bacteriological Sample Point	2	EA		\$ -
SECTION 2 SUBTOTAL:					\$ -
SECTION 3: RESTORATION (WATER MAIN)					
ITEM NO.	DESCRIPTION	EST. QUANT	UNIT	UNIT PRICE	EXTENDED PRICE
14	General Restoration	8,497	LF		\$ -
15	Roadway Restoration				
a.	Trench Restoration	40	SY		\$ -
b.	Mill & Overlay (Collector Roadways)	472	SY		\$ -
16	Remove & Replace Concrete Walk	37	SY		\$ -
SECTION 3 SUBTOTAL:					\$ -

SECTION 4: FORCE MAIN SYSTEM					
ITEM NO.	DESCRIPTION	EST. QUANT	UNIT	UNIT PRICE	EXTENDED PRICE
17	Force Main Pipelines (Via Open-Cut)				
a.	4-inch PVC DR18	30	LF		\$ -
b.	6-inch PVC DR18	7,565	LF		\$ -
18	Plug Valves				
a.	6" Plug Valve	12	EA		\$ -
19	Connect to Existing Force Main				
a.	6-inch WM (Cut In Existing)	1	EA		\$ -
b.	8-inch WM (Cut In Existing)	1	EA		\$ -
SECTION 4 SUBTOTAL:					\$ -
SECTION 5: ALLOWANCE					
ITEM NO.	DESCRIPTION	EST. QUANT	UNIT	UNIT PRICE	EXTENDED PRICE
20	General Allowance	1	T&M	\$ 300,000.00	\$ 300,000.00
SECTION 5 SUBTOTAL:					\$ 300,000.00
SECTION 6: CLEARING AND GRUBBING					
ITEM NO.	DESCRIPTION	EST. QUANT	UNIT	UNIT PRICE	EXTENDED PRICE
21	Clearing and grubbing along Golf Course alignment	1	LS		\$ -
SECTION 6 SUBTOTAL:					\$ -
SUMMARY					
SECTION 1: GENERAL:					\$ -
SECTION 2: WATER SYSTEM:					\$ -
SECTION 3: RESTORATION (WATER MAIN):					\$ -
SECTION 4: FORCE MAIN SYSTEM:					\$ -
**SECTION 5: ALLOWANCE:					\$ 300,000.00
SECTION 6: RESTORATION CLEARING AND GRUBBING:					\$ -
TOTAL:					\$ 300,000.00

**See Technical Specifications Section 01026 Measurement and Payment for Bid Item Descriptions.*

The Contractor shall be required to pick up materials purchased by the County and deliver it to the site. Ductile Iron pipe and valves are located at: Collier County Operations Center, 4781 Green Boulevard, Naples, FL HDPE pipe is located at: Raw Water Booster Station, 841 7th Street SW, Naples, FL

****Owner Allowance will be used only at the Owner's direction to accomplish work due to unforeseen conditions and/or as directed by the Owner. Inclusion of the Allowance as part of the Contract Price is not a guarantee that the Contractor will be paid any portion or the full amount of the Allowance. Expenditures of the Owner's Allowance will be made through Change Order with Proper documentation of Time and Materials supporting the change.**