

23-8190 Bid Schedule
Master Pump Station (MPS) 302 Forcemain Replacement

| Line No. | Description | Quantity | Unit | Unit Price | Total Price |
|---|---|----------|------|------------|-------------|
| <i>Site Work</i> | | | | | |
| 1 | Mobilization | 1 | LS | \$ - | \$ - |
| 2 | Silt Fence | 1,562 | LF | | \$ - |
| 3 | Drop Inlet Sediment Barrier | 2 | EA | | \$ - |
| 4 | Pre/Post-Audio Video Recording | 1 | LS | | \$ - |
| 5 | Maintenance of Traffic | 1 | LS | | \$ - |
| 6 | Survey Stake-out/ Survey As-built | 1 | LS | | \$ - |
| 7 | Private Utility Locates/Potholing | 1 | LS | | \$ - |
| 8 | Removal of Existing Concrete | 173 | SY | | \$ - |
| 9 | Removal of Existing Asphalt | 1,030 | SY | | \$ - |
| 10 | Clearing and Grubbing | 0.20 | AC | | \$ - |
| 11 | Geotechnical Testing | 1 | LS | | \$ - |
| 12 | Dewatering | 1 | LS | | \$ - |
| 13 | Sod - Bahia | 1 | LS | | \$ - |
| 14 | Underground Electric and Fiber Optic Relocation | 1 | LS | | \$ - |
| Site Work Subtotal | | | | | \$ - |
| <i>Pavement, Concrete, Striping, and Signage</i> | | | | | |
| 15 | Sidewalk - 6" Concrete | 103 | SY | | \$ - |
| 16 | 12" Stabilized Sub-Grade | 1,133 | SY | | \$ - |
| 17 | Asphalt | 1,030 | SY | | \$ - |
| 18 | Asphaltic Concrete | 1,030 | SY | | \$ - |
| 19 | Type F Curb | 160 | LF | | \$ - |
| 20 | Type B Curb | 100 | LF | | \$ - |
| 21 | 2' Valley Gutter | 51 | LF | | \$ - |
| Pavement, Concrete, Striping, and Signage Subtotal | | | | | \$ - |
| <i>Utilities</i> | | | | | |
| 22 | Connection to Existing Force Main | 2 | EA | | \$ - |
| 23 | Connection to Existing IQ Main | 2 | EA | | \$ - |
| 24 | 36" DR-11 HDPE Forcemain Pipe | 295 | LF | | \$ - |
| 25 | 30" DR-11 HDPE IQ Main Pipe | 71 | LF | | \$ - |
| 26 | IQ Air Release Valve | 1 | EA | | \$ - |
| 27 | FM Air Release Valve | 1 | EA | | \$ - |
| 28 | Utility Marker Balls | 1 | LS | | \$ - |
| 29 | Exploration/Video of the Existing 36" Forcemain | 1 | LS | | \$ - |
| Utilities Subtotal | | | | | \$ - |
| <i>Landscape</i> | | | | | |
| 30 | Landscaping | 1 | LS | | \$ - |
| 31 | Irrigation | 1 | LS | | \$ - |
| Landscape Subtotal | | | | | \$ - |
| Total Bid Price | | | | | \$ - |

*Staff has allocated \$150,000 in Owner's Allowance - for Owners Use as Directed. This Allowance will be used only at the Owner's direction to accomplish work due to unforeseen conditions and/or as directed by the Owner. Inclusion of the Allowance as part of the Contract Price is not a guarantee that the Contractor will be paid any portion or the full amount of the Allowance. Expenditures of Owners Allowance will be made through Change Order with proper documentation of Time and Materials supporting the change.