

## Palm River Public Utilities Renewal Project - Area 4

### Bid Schedule

#### Construction ITB 24-8227

ITEM NO.	DESCRIPTION	UNIT	UNIT PRICE	EST. QTY.	TOTAL PRICE
<b>SECTION 1: GENERAL</b>					
1.1	Mobilization/Demobilization (Max 10% of Total Bid Amount)	LS		1	\$0.00
1.2	Maintenance of Traffic	LS		1	\$0.00
1.3	Survey Layout & Record Drawings	LS		1	\$0.00
1.4	Pre-Construction Video & Photographs	LS		1	\$0.00
1.5	Post-Construction Video	LS		1	\$0.00
1.6	Clearing & Grubbing	LS		1	\$0.00
1.7	Vibratory Monitoring	LS		1	\$0.00
1.8	Road Restoration - Stabilized Subgrade	SY		7,300	\$0.00
1.9	Road Restoration - Limerock Base (6")	SY		7,000	\$0.00
1.10	Road Restoration - 2-1/2" Asphalt (Two Lifts)	SY		6,700	\$0.00
1.11	Final Pavement Striping, Marking, and Signs	LS		1	\$0.00
1.12	Remove, Dispose, and Replace Concrete Curb (Valley Gutter)	LF		168	\$0.00
1.13	Milling & Resurfacing	SY		336	\$0.00
1.14	Replace/Restore Drainage Infrastructure	LF		100	\$0.00
1.15	Remove, Dispose, and Replace Driveways on Old Tamiami Trail	SY		160	\$0.00
<b>SECTION 1 (GENERAL) SUBTOTAL:</b>					<b>\$0.00</b>
<b>SECTION 2: WATER SYSTEM</b>					
2.1	<b>Water Main Pipelines</b>				
i.	6-inch C900 DR14 PVC	LF		150	\$0.00
ii.	8-inch C900 DR14 PVC	LF		2,000	\$0.00
iii.	10-inch C900 DR14 PVC	LF		1,500	\$0.00
2.2	<b>Gate Valves</b>				
i.	6-inch Gate Valve	EA		1	\$0.00
ii.	8-inch Gate Valve	EA		4	\$0.00
iii.	10-inch Gate Valve	EA		5	\$0.00
2.3	<b>Fire Hydrant Assemblies</b>	EA		9	\$0.00
2.4	<b>2" Water Services</b>	EA		28	\$0.00
2.5	<b>Water Meter Boxes and Backflow Devices</b>	EA		26	\$0.00
2.6	<b>Water Meter Boxes (vacant property)</b>	EA		2	\$0.00
2.7	<b>Connection to Existing Water Main</b>				
i.	6" AC WM Cocohatchee Boulevard and Old Tamiami Trail	EA		1	\$0.00
2.8	<b>Air Release Valves</b>	EA		3	\$0.00
2.9	<b>Conflict Avoidance (Deflection)</b>	EA		4	\$0.00
2.10	<b>Abandon, Cap, and Grout Fill Existing 6" Water Main</b>	LF		3,650	\$0.00
2.11	<b>Remove and Disposal of Asbestos Concrete Water Main</b>	LF		500	\$0.00
<b>SECTION 2 (WATER SYSTEM) SUBTOTAL:</b>					<b>\$0.00</b>

ITEM NO.	DESCRIPTION	UNIT	UNIT PRICE	EST. QTY.	TOTAL PRICE
<b>SECTION 3: WASTEWATER SYSTEM</b>					
<b>3.1</b>	<b>Sanitary Sewer Force Main</b>				
i.	2" HDPE Force Main Open Cut	LF		1,800	\$0.00
ii.	3" HDPE Force Main Open Cut	LF		1,700	\$0.00
iii.	3" HDPE Force Main HDD	LF		1,000	\$0.00
<b>3.2</b>	<b>Conflict Avoidance (Deflection)</b>	EA		4	\$0.00
<b>3.3</b>	<b>Plug Valves</b>				
i.	3-inch plug valve	EA		4	\$0.00
ii.	4-inch plug valve	EA		1	\$0.00
<b>3.4</b>	<b>Air Release Valves</b>	EA		4	\$0.00
<b>3.5</b>	<b>Force Main Maintenance Ports</b>				
i.	Terminal Maintenance Port	EA		2	\$0.00
ii.	In-line Maintenance Port	EA		3	\$0.00
<b>3.6</b>	<b>Connection to Existing Force Main (8" Cast Iron)</b>				
i.	PS-103.10 Discharge Piping on Viking Way	EA		1	\$0.00
<b>3.7</b>	<b>Low Pressure Service Laterals &amp; Connection Boxes</b>	EA		27	\$0.00
<b>3.8</b>	<b>Low Pressure Collection System &amp; Permitting</b>	EA		27	\$0.00
<b>3.9</b>	<b>Grinder Pump Station Electrical Service &amp; Permitting</b>	EA		27	\$0.00
<b>3.10</b>	<b>Electrical Panel Upgrades</b>	EA		5	\$0.00
<b>3.11</b>	<b>Septic Tank Abandonments</b>	EA		27	\$0.00
<b>SECTION 3 (WASTEWATER SYSTEM) SUBTOTAL:</b>					<b>\$0.00</b>
<b>SUMMARY</b>					
<b>Section 1: General</b>					<b>\$0.00</b>
<b>Section 2: Water System</b>					<b>\$0.00</b>
<b>Section 3: Wastewater System</b>					<b>\$0.00</b>
<b>TOTAL BID AMOUNT:</b>					<b>\$0.00</b>

\* Staff has allocated \$320,000.00 in Owner's Allowance - for Owners Use as Directed. This Allowance will be used only at the Owner's direction to accomplish work due to unforeseen conditions and/or as directed by the Owner. Inclusion of the Allowance as part of the Contract Price is not a guarantee that the Contractor will be paid any portion or the full amount of the Allowance. Expenditures of Owners Allowance will be made through Change Order with proper documentation of Time and Materials supporting the change.