

NCRWTP RAW WATER FEEDLINE REHAB PHASE 1 AND PHASE 2**CONSTRUCTION ITB No. 24-8320****BID SCHEDULE**

Bid items include all items described in the Summaries of Work and Measurement and Payment specifications for Phase 1 and Phase 2 work as shown on the attached Drawings and Exhibits with no substitutions or limitations.

Phase 1 Raw Water Line Refurbishment

ITEM NO	DESCRIPTION	QUANTITY	Units	TOTAL
1	General Requirements and Conditions/Mobilization/Demobilization (Phase 1)	1	LS	
2	Procurement and installation of a new static mixer, and associated piping, in chemical injection vault as shown on the plans as well as disinfection prior to use.	1	LS	
3	Mobilization and demobilization of Phase 1 temporary by-pass piping, disinfection prior to use and disposal of associated materials at completion.	1	LS	
4	Demolition and replacement of raw water line from the chemical injection vault to the wall of the process building, disinfection prior to use, refurbishment of area including sodding, and disposal of associated demolished materials.	1	LS	
5	Refurbishment of the concrete encased portion of the raw water line using a specialty composite material and disinfection prior to use.	1	LS	
6	Demolition and replacement of the raw water line in the pipe trench inside the process area from the connection to the concrete encased portion of rehabilitated raw water line to the connection points with five cartridge filters and disposal of associated demolished materials.	1	LS	
Sum of Phase 1 Bid Items 1 through 6:				\$0

Phase 2 Raw Water Line Refurbishment

7	General Requirements and Conditions/Mobilization/Demobilization (Phase 2)	1	LS	
8	Mobilization and demobilization of Phase 2 temporary by-pass piping including disinfection prior to use and disposal of associated materials at completion.	1	LS	
9	Demolition and replacement of raw water line from the exit of the cartridge filters to the influent of the NF pump cans (six connection points) inclusive of supports, connections, disinfection as well as reinstallation of sensor and disposal of associated demolished materials.	1	LS	
Sum of Phase 2 Bid Items 7 through 9:				\$0
TOTAL BID AMOUNT (Phase 1 & 2):				\$0

Basis of award shall be the Total Bid Price inclusive of Phase 1 and Phase 2 bid items (sum of bid items 1 through 9).

*Staff has allocated an Owner's Allowance for Phase 1 and for Phase 2 work. The Owner's Allowance for Phase 1 is \$110,000 and the Owner's Allowance for Phase 2 is \$150,000 - for Owners Use as Directed. These Allowances will be used only at the Owner's direction to accomplish work due to unforeseen conditions and/or as directed by the Owner. Inclusion of the Allowance as part of the Contract Price is not a guarantee that the Contractor will be paid any portion of the full amount of the Allowance. Expenditures of Owner's Allowance will be made through Change Order with proper documentation of Time and Materials supporting the change.