

BID SCHEDULE
Construction ITB #25-8429
Poinciana Village Stormwater Improvements

Bidder's Name: _____
Bid Date: _____

ROADWAY PLANS

Item No.	Description	Units	Bid Quantity	Unit Price	Bid Amount
101-1	Mobilization (Prorated)	LS	1		\$ -
102-1	Maintenance of Traffic (Prorated)	LS	1		\$ -
104-10-3	Sedimentation Barrier	LF	26,074		\$ -
104-18	Inlet Protection System	EA	67		\$ -
110-4-10	Removal of Existing Concrete	SY	715		\$ -
110-1-1	Clearing & Grubbing	AC	4		\$ -
120-10-21	Clean & Reshape Ditch	LF	8,460		\$ -
121-70	Flowable Fill	CY	1,533		\$ -
145-1	Geosynthetic Reinforced Soil Slopes	SY	31,534		\$ -
210-2	Limerock, New Material for Reworking Base (18")	SY	1,822		\$ -
334-1-13	Superpave Asphaltic Concrete (SP-12.5)	TN	995		\$ -
425-1-521	FDOT Type C Inlet, <10'	EA	21		\$ -
425-1-551	FDOT Type E Inlet, <10'	EA	34		\$ -
425-1-571	FDOT Type G Inlet, <10'	EA	11		\$ -
425-1-711	FDOT Gutter Type V, <10'	EA	1		\$ -
430-175-118	Pipe Culvert, Optional Material, Round (18" RCP)	LF	122		\$ -
430-175-118A	Pipe Culvert, Optional Material, Round (18" HP)	LF	426		\$ -
430-175-124	Pipe Culvert, Optional Material, Round (24" RCP)	LF	114		\$ -
430-175-130	Pipe Culvert, Optional Material, Round (30" RCP)	LF	71		\$ -
430-175-215	Pipe Culvert, Optional Material, Ellip. (15" ERCP)12x18	LF	650		\$ -
430-175-218	Pipe Culvert, Optional Material, Ellip. (18" ERCP)14x23	LF	996		\$ -
430-175-224	Pipe Culvert, Optional Material, Ellip. (24" ERCP)19x30	LF	2,031		\$ -
430-175-230	Pipe Culvert, Optional Material, Ellip. (30" ERCP)24x38	LF	753		\$ -
430-830	Filling and Plugging Pipe-Place out of Service	CY	29		\$ -
430-984-125	Mitered End Section (18")	EA	1		\$ -
430-984-623	Mitered End Section (12"x18")	EA	8		\$ -
430-518-100	Concrete Headwell (18")	EA	1		\$ -
430-524-102	Concrete Headwell (19"x30")	EA	15		\$ -
430-530-112	Concrete Headwell (24"x38")	EA	4		\$ -
520-3	Concrete Valley Gutter	LF	20		\$ -
522-1	Concrete Sidewalk, 4" Thick	SY	199		\$ -
522-2	Concrete Sidewalk & Driveway, 6" Thick	SY	516		\$ -
570-1-2	Preformance Turf, Sod	SY	40,129		\$ -
711-11-125	Thermoplastic, STD, White, Solid, 24"	LF	169		\$ -
711-15-101	Thermoplastic, STD, White, Solid, 6"	GM	0.02		\$ -
711-15-201	Thermoplastic, STD, Yellow, Solid, 6"	GM	0.30		\$ -
SP-1	Utility Conflict, 6" AC Watermain	EA	9		\$ -
SP-2	Utility Adjust Water Service	EA	14		\$ -
SP-3	Utility Conflict, 6" Forcemain Removal	EA	9		\$ -
SP-4	Utility Adjust Sewer Service	EA	1		\$ -
SP-5	Remove and Reset Paver Driveway	SF	250		\$ -
SP-6	Hold/Protect Light Pole	EA	7		\$ -
SP-7	Landscape Hedge	LS	1		\$ -
SP-8	Construction Video/Assessment (Prorated)	LS	1		\$ -
SP-9	Project Sign	EA	3		\$ -
SP-10	Record Survey (Prorated)	LS	1		\$ -
SP-11	Playground Equipment - Remove & Reinstall	LS	1		\$ -
			Total Bid Amount		\$ -
			Owner's Allowance (10% of Total Bid)		\$ -

Staff will allocate 10% for Owner's Allowance - for Owners Use as Directed. This Allowance will be used only at the Owner's direction to accomplish work due to unforeseen conditions and/or as directed by the Owner. Inclusion of the Allowance as part of the Contract Price is not a guarantee that the Contractor will be paid any portion or the full amount of the Allowance. Expenditures of Owners Allowance will be made through Change Order with proper documentation of Time and Materials supporting the change.