

Bid Schedule
 Phase 1 - Carica WM Connection
 Transmission Water Main Improvements
 Vanderbilt Beach Road Airport Pulling Road

SECTION 1: GENERAL					
ITEM NO.	DESCRIPTION	EST. QUANT.	UNIT	UNIT PRICE	EXTENDED PRICE
1	Mobilization/Demobilization (<i>Not to Exceed 10% of the Total Base Bid</i>)	1	LS		
2	Survey Layout & Record Drawings	1	LS		
3	Pre-Construction Video Recording	1	LS		
SECTION 1 SUBTOTAL:					
SECTION 2: WATER SYSTEM					
ITEM NO.	DESCRIPTION	EST. QUANT.	UNIT	UNIT PRICE	EXTENDED PRICE
4	Install 30" DIP CL250 Water Main Pipelines Via Open-Cut	240	LF		
5	Install 30" Gate Valve	3	EA		
6	Connect to Existing 30" PCCP Water Main (PCCP-DIP Adapter)	1	EA		
7	Connect to Existing 30" DIP Water Main				
a.	30" DIP WM (Remove Adapter, Connect to DIP Sleeve)	1	EA		
b.	30" DIP Fill Line (Cut in 45°)	1	EA		
8	Abandon and Remove Existing Water Main				
a.	Existing 30" PCCP Water Main	180	LF		
b.	Existing 30" DIP Water Main	100	LF		
9	Abandon and Grout Existing 30" DIP Water Main	180	LF		
SECTION 2 SUBTOTAL:					
SECTION 3: ALLOWANCE					
ITEM NO.	DESCRIPTION	EST. QUANT.	UNIT	UNIT PRICE	EXTENDED PRICE
10	General Allowance for Unforeseen Conditions - Owner Directed	1	T&M	\$ 75,000.00	\$ 75,000.00
SECTION 3 SUBTOTAL:					\$ 75,000.00
SUMMARY					
SECTION 1: GENERAL					
SECTION 2: WATER SYSTEM					
SECTION 3: ALLOWANCE					\$ 75,000.00
TOTAL:					

Collier County is providing a portion of the materials for the water main pipeline installation. The contractor is responsible for providing any materials, or material quantities, necessary to complete the project that are not included in the list of County Purchase Materials identified in *Project Manual Section 3.4*.