

**ADDENDUM # 3**

**Date:** October 13, 2020  
**From:** Alicia Abbott  
**To:** Potential Bidders  
**Subject:** Addendum # 3 – SRO Wellfield Wells 19-21 Electrical Improvements Project Agreement 19-7527 Electrical Contractors with Public Utilities Specialization

This addendum has been issued for the following item(s) identifying clarifications, changes, deletions, or additions to the original solicitation documents and bid schedule for the above referenced solicitation.

- The Request for Quote Due Date of October 15, 2020 at 3:00p.m. is changed to Friday, October 16, 2020, at 3:00 p.m.
- The three conductors and ground within two of the existing conduits, were removed previously. **There are currently three conductors and ground remaining in only one of the conduits.** These will need to be removed and disposed of (credit to be provided).
- Provide red dye in the concrete protective cap for easy identification during subsequent excavation.
- A warning ribbon should be placed in the trench not less than 12" above the underground installation.
- Correction to the previous Question 8:  
**Is the County purchased conduit chamfered? New Response: Yes.**  
The 4" Schedule 80 conduit was delivered, and is chamfered on one end, with a bell end on the other end.
- The j-boxes are to be grounded to existing grounding.
- Additional 4/0 cable is added to the material list of items to be provided by the county.
- 1900ft. Southwire 4-7CU (221.2MM2) SIMPULL R XHHW-2 (includes cut charge), is changed to 1900ft. Southwire 4/0-19CU XHHW-2-Black.  
A revised material list is attached.

**Please acknowledge receipt of this Addendum and include with your bid.**

\_\_\_\_\_  
(Signature)

\_\_\_\_\_  
Date

\_\_\_\_\_  
(Name of Firm)