

POLK COUNTY UTILITIES DIVISION
CR 547 RECLAIMED WATER MAIN IMPROVEMENTS PHASE 1
BID 19-284
BID SHEET

No.	Description	Unit	QTY	Unit Price	Price
1	Reclaimed Water Main				
	a) 12" C900 DR18 Polyvinyl Chloride (PVC) (Open Cut)	LF	2,112		\$ -
2	Fittings				
	a) 12" 90° Bend, MJ	EA	9		\$ -
	b) 12" 45° Bend, MJ	EA	2		\$ -
	c) 12" 11.25° Bend, MJ	EA	11		\$ -
	d) 12" HDPE Adapter	EA	6		\$ -
	e) 16"x12" Tee	EA	1		\$ -
3	Valves				
	a) 12" Gate Valve & Box	EA	9		\$ -
4	Connections				
	a) Connections to Existing Reclaimed Water Mains	EA	4		\$ -
5	Horizontal Directional Drill				
	a) 12" High Density Polyethylene (HDPE) DR11	LF	3,168		\$ -
6	Jack and Bore				
	a) 12" C900 PVC DR18 Carrier Pipe with 24" Steel Casing	LF	200		\$ -
7	Sodding				
	a) Sodding	SY	3,550		\$ -
8	Asphalt Pavement Removal and Replacement				
	a) Driveway Pavement Removal/Replacement	SY	82		\$ -
	b) Roadway Pavement Removal/Replacement	SY	50		\$ -
	c) Milling and Resurfacing	SY	512		\$ -
9	Concrete Removal and Replacement				
	a) Driveway Pavement Removal/Replacement	SY	15		\$ -
	b) Sidewalk Removal/Replacement	LF	168		\$ -
10	Gravel Driveway Removal and Replacement				
	a) Driveway Pavement Removal/Replacement	SY	30		\$ -
11	Miscellaneous Items	LS	1		\$ -
12	Maintenance of Traffic	LS	1		\$ -
13	Environmental Protection	LS	1		\$ -
14	Mobilization/Demobilization	LS	1		\$ -
15	As-Built Survey Drawings	LS	1		\$ -
	SUBTOTAL				\$ -
15	Contingency for Unsuitable Soils	LS	1	\$ 25,000.00	\$ 25,000.00
16	Contingency for Existing Utility Relocation	LS	1	\$ 25,000.00	\$ 25,000.00
17	Contingency for Unknown Conditions	LS	1	\$ 25,000.00	\$ 25,000.00
	Grand Total				\$ 75,000.00