



RRBP Site Development (Phase 1A -Deep Injection Well - Water Main)				5/14/2019
Opinion of Probable Cost				
Scope of Work	Quantity	Unit	Unit Price	Total Price
Initial Site Design				
1 Mobilization	1	LS		\$ -
2 Construction Stake-Out and As-Builts Survey	1	LS		\$ -
TOTAL INITIAL SITE WORK CONSTRUCTION				\$ -
Water Utilities				
3 Temporary 8" CL200 DR14 PVC	600	LF		\$ -
4 12" CL200 DR14 PVC	1,929	LF		\$ -
5 Fittings	1	LS		\$ -
6 12" Gate Valves	2	EA		\$ -
7 Fire Hydrant Assembly w/Valve	4	EA		\$ -
8 12" Blow-off Assembly	2	EA		\$ -
9 Permanent Bacterial Sample Point	1	EA		\$ -
10 Automatic Flushing Device	1	EA		\$ -
11 Geotech and Rock Excavation	1	LS		\$ -
TOTAL WATER UTILITIES CONSTRUCTION (Base Bid)				\$ -
Bid Alternatives				
12 8" CL200 DR14 PVC	112	LF		\$ -
13 10" CL200 DR14 PVC	40	LF		\$ -
14 Fittings	1	LS		\$ -
15 10" Gate Valves	2	EA		\$ -
16 8" Gate Valves	8	EA		\$ -
17 8" Blow-off Assembly	8	EA		\$ -
18 10" Blow-off Assembly	1	EA		\$ -
TOTAL BID ALTERNATIVE CONSTRUCTION				\$ -
Base Bid + Allowance (10%)				\$ -
Base Bid + Alternate +Allowance (10%)				\$ -