

NO	PAY ITEM DESCRIPTION	UNIT	QTY	Unit Price	Total
1	Mobilization / Demobilization	LS	1		
2	General Requirements (Including Dewatering Permit, Clearing, Erosion Control Program, and Demolition Items)	LS	1		
3	Surveying (Including Construction Layout, Pre-Excavation, Earthwork Quantity Calculations, and Record Drawings)	LS	1		
4	Silt Fencing	LF	5,400		
5	Floating Turbidity Barriers	LF	280		
6	Excavation / Embankment (Including Grading at Structures, Canal Connections, and 6-inch Top Soil Removal, Storage, & Replacement)	CY	172,500		
7	57 Stone (6" thick at structures along fence line)	SY	25		
8	5-Strand Barbed Wire Fencing	LF	2,445		
9	Painted 2-inch Tube Swing Gates (16 LF each) (Including Heavy Duty Mounting Posts)	EA	4		
10	6' Chain Link Fence w/ 3 Strands of Barbwire Installed (Green Coated)	LF	64		
11	6' High x 6' Wide Slide Gates w/ 3 Strands of Barbwire Installed (Green Coated)	EA	6		
12	48" x 76" Elliptical Reinforced Concrete Pipe	LF	612		
13	24" Reinforced Concrete Pipe	LF	101		
14	Double 60" RCP Straight Concrete Endwall, Modified for Double 48" x 76" ERCPs (S-1 & S-5), Including Concrete and Reinforcing Steel	EA	2		
15	48" x 76" Mitered End Section, Double (S-2 & S-6) (includes 38 LF of Pipe)	EA	2		
16	Double 60" RCP Straight Concrete Endwall, Modified for Single 24" RCP (S-3), Including Concrete and Reinforcing Steel	EA	1		
17	24" Mitered End Section, Single (S-4) (includes 11 LF of Pipe)	EA	1		
18	Aluminum Slide Gate for 48" x 76" ERCP, Bottom-Up & Manually Operated	EA	4		
19	Aluminum Slide Gate for 24" x 24" RCP, Bottom-Up & Manually Operated	EA	1		
20	Stabilized Soil, 6" (LBR 40, 98% Density) (Perimeter Berm, Interior Maintenance Paths, and Entrances)	SY	19,325		
21	Restoration Sodding (Bahia for Berm to EL. 19.0' and at Structures & Canal Connection)	SY	28,700		
22	Permanent 4" Bronze Benchmark (Elevation Set by P.S.M. to NGVD 29 Datum)	EA	3		
23	Rip-Rap (8" Filter Point Fabric-Formed Concrete Rip-Rap)	SF	5,814		
24	Concrete Sidewalk, 6" (with 6" Stabilized Subgrade 40 LBR)	SY	33		
25	Pedestrian, Bicycle Railing, Aluminum (Speed Rail System)	LF	113		
26	Object Marker, Type 4 (OM4-1, 18"x18")	EA	24		
27	Planted swale and wide swamp Area (Shrubs and Groundcover), 3' O.C.	EA	10,096		
28	Planted Swale and Wide Swamp Area (Trees), 3 Gallon, 15' O.C.	EA	538		
29	Planted Area (Shrubs and Groundcover), 3' O.C.	EA	1,569		
30	Planted Area (Trees), 3 Gallon, 15' O.C.	EA	84		
31	Planted Upland (Shrubs and Groundcover), 3' O.C.	EA	2,466		
32	Planted Upland (Trees), 3 Gallon, 15' O.C.	EA	132		
33	I-Beam (with Staff Gauge)	EA	1		
Total Bid Price (Total of all Lump Sum and Unit Price Bids):					