



SOUTH FLORIDA WATER MANAGEMENT DISTRICT SOLICITATION ADDENDUM

South Florida Water Management District
Attn: Procurement Bureau
B-1 Building, 2nd Floor West
3301 Gun Club Road
West Palm Beach, FL 33406

SOLICITATION NUMBER: 6000001074

ADDENDUM NUMBER: 2

DATE: August 19, 2020

Project Title: S-291 SCADA Retrofit & Automation Project, Glades County, Florida

This **ADDENDUM NO. 2** is issued for the purpose of providing the following information below.

- 1. DEADLINE FOR EMAIL BID SUBMISSION: DEADLINE FOR BID SUBMISSION REMAINS AUGUST 26, 2020 @ 2:30 P.M. BIDS WILL BE ACCEPTED VIA EMAIL TRANSMISSION.**

RESPONSES WILL ONLY BE ACCEPTED VIA EMAIL TRANSMISSION. HAND DELIVERED OR PACKAGES MAILED VIA U.S. MAIL OR OVERNIGHT COURIER WILL NOT BE ACCEPTED WHILE THE DISTRICT REMAINS CLOSED TO THE PUBLIC.

- 2. DATE AND PLACE OF BID OPENING:**

The novel Coronavirus (COVID-19) has created a public health emergency throughout the entire State of Florida. Governor Ron DeSantis' Executive Order 20-52 and the South Florida Water Management District (SFWMD) Emergency Authorization 2020-004-DAO allow for the District to modify its normal procurement practices and policies to protect the public from the threat posed by COVID-19. Given that the Florida Department of Health (DOH) and Centers for Disease Control and Prevention (CDC) recommend not holding in-person meetings, the SFWMD will proceed with the following bid submittals and openings as follows:

SFWMD will accept bids submitted on the date and time set forth above via email to Procurement@sfwmd.gov. An auto-generated response documenting receipt of your submittal will be sent to your email address. If a Respondent does not receive the auto-generated response within 5 minutes of bid submittal, please contact Procurement at 561-682-2011. To ensure proper receipt of responses, Respondent must:

1. Identify the solicitation number and title in the subject line of the email.
2. Convert bid submittal document to pdf file format.
3. Submit one bid response in one single email. If multiple documents are being submitted that require more than one email, label each email 1 of 2, 2 of 2, etc.

The SFWMD assumes no responsibility for responses not properly marked.

Preliminary results will be posted on the SFWMD website, [https://www.sfwmd.gov/doing-business-with-us/procurement following the bid opening](https://www.sfwmd.gov/doing-business-with-us/procurement-following-the-bid-opening).

- 3. QUESTIONS AND ANSWERS:** Attachment 1 to this Addendum No. 2 contains the list of Questions and Answers

Please direct any questions to the Procurement Representative specified below at (561) 682-6373 or gjolly@SFWMD.GOV.

Gina Jolly
Senior Contract Specialist
Procurement Department

ATTACHMENT 1
RFB 6000001074- ADDENDUM NO. 2
QUESTIONS AND ANSWERS

1. **Question:** Can you please status the pending permits (USACE 404, FDEP Exemption, USACE 408):
Answer: The District has received the 404 and 408 permits, per FDEP this project is under a larger FDEP permit which has also been obtained.

2. **Question:** Drawing C006 – Please confirm that there should be a 4’ gate on the NW side of the fence, where the drawings state “4’ – 0” Security Fence”:
Answer: Yes. Refer to Drawing C006, a 4’ gate on the NW side of the fence is required.

3. **Question:** S-001 – Special Inspections, Note 1 & 2. Are the Special inspections the responsibility of the District?
Answer: The Special inspections are the responsibility of the Contractor.

4. **Question:** General Note 1 states that the minimum pile embedment is 10’, however the farthest two piles from shore, indicate minimum of 15’ embedment in Elevation K. Please confirm the Elevation K drawing is correct?
Answer: Refer to Drawing S007, the Elevation K drawing is correct, 10’ is the minimum pile embedment length, and 15’ is required for the two piles.

5. **Question:** S-007 – General Note 8 states that all field welds must be inspected and tested by an independent testing laboratory. Are the field weld inspections the responsibility of the District?
Answer: The field weld inspections are the responsibility of the Contractor.

6. **Question:** What is the required notification time for the ACOE to be present during the transition (cutover) to the new SFWMD Motorola ACE SCADA system?
Answer: The SFWMD PM and SCADA should be notified to be present during the transition (cutover). The Headwater section is solely the responsibility of the SFWMD.

7. **Question:** M008 – Generator Exhaust Piping Elevation 1 and 2 shows a 50kw generator, please confirm a new 25kw generator is required?
Answer: Refer to Technical Specification 16620

8. **Question:** Drawing C-003 provides coordinates for the edge of the Antenna Pole Pad. Drawing I010 provides the dimensions of the antenna Pole pad and location of the antenna pole plan. General Note 7 on Drawing I1010 states that the Pole(s) should not be closer than 14’ from any canal, top of berm. Please confirm that the pole location is to be per the coordinates provided on Drawing C-003:
Answer: Refer to Drawing I1010 for the dimensions of the antenna Pole pad. Drawings C003 and C006 indicates the location of the antenna pole pad. The pole location is to be per the coordinates provided on Drawing C-003.

9. **Question:** Technical Specification and Contract drawings C008 require that Concrete Piles shall have CCW admixture in the concrete mix. Is this the only concrete on the project that requires CCW? In addition, please confirm that permeability test results (030501.03 C 4) are not required to be submitted for only the Concrete Piles:

Answer: Refer to Tech Spec 02367 for Crystalline Capillary Waterproofing (CCW) admixture. Refer to 03050 1.03 C 4 and 2.02 B for the permeability test required.