



# SOUTH FLORIDA WATER MANAGEMENT DISTRICT SOLICITATION ADDENDUM

South Florida Water Management District  
Attn: Procurement Department  
B-1 Building, 2<sup>nd</sup> Floor West  
3301 Gun Club Road  
West Palm Beach, FL 33406

**Request for Proposal (RFP) Number: 6000000909**

**ADDENDUM NUMBER: 1**

**DATE: August 6, 2018**

**Project Title: C-43 RESERVOIR GROUNDWATER MONITORING INSTALLATION**

**Deadline For Proposal Submission Remains at August 14, 2018 - 2:30 P.M.**

This **ADDENDUM NO. 1** is issued for the purpose of providing answers to questions received during the inquiry period for the above titled RFP.

Questions asked during the inquiry period:

Q1. The objective of the statement of work states to install CR1000 RTU's and Well Monitoring Transducers. The table in Section 8 list equipment that the District is providing. Is the Contractor required to provide the Campbell Scientific CR1000 dataloggers and groundwater monitoring pressure transducers?

A1. The District will install the CR1000 panels and Instruments. Contractor is to perform the rough in work.

Q2. The table in Section 8 states that the District will provide one (1) of each of the following: RTU enclosure, solar panel with mounting brackets, cell antenna with mounting brackets, ion dissipater, polyphaser. There are 22 different sites. Is the District providing 1 of each item or 1 of each item per site (22 total)?

A2. The District will provide 22 sets, one set of items for each site

Q3. For site C43225 the statement of work states that the existing bollards are to be removed. On the other sites that have bollards, are they to be left in place and incorporated into the 6 bollard pattern around the site or are 6 new bollards to be installed at all sites?

A3. At the other sites the existing bollards shall be left in place or repaired and added to complete the pattern

Please direct any questions to the Procurement Representative specified below at (561) 682-6420 or [ddixon@sfwmd.gov](mailto:ddixon@sfwmd.gov).

Dora Dixon  
Senior Contract Specialist